Conley House 4919 Montgomery Road HO-344

Located on 1.5 acres on the north side of Montgomery Road east of the intersection of Route 103, this 2 1/2 story late-Victorian house was built about 1890. Arranged in a massed plan, three bays long and two bays wide with an ell, the gabled structure displays the popular rural vernacular center gable and wrap-around porch.

This house is significant as one of the last remaining examples of late 19th century victorian rural vernacular architecture along Montgomery Road.

Montgomery Road has historically been an important thoroughfare in Howard County linking Ellicott City (via Columbia Pike) with Elk Ridge, once a major inland port. Today the house represents the last vestige of a rural environment along what is now a densely developed corridor. While the lot is small the mature trees provide a buffer from the road.

HO-344 The Handwerk House Ellicott City Private

The Handwerk House faces south on the north side of Montgomery Road or Route 103, just east of its intersection with Route 104.

It is a three bay wide, two room deep, two and a half story high, frame (covered with asbestos shingles), gabled roof (running east-west) house, resting on a stone foundation, with a two bay wide, one room deep, two story high, intersectinggable roof (running north-south) frame kitchen wing off the east side of its north wall, which creates an "L" plan.

Square, brick corbeled chimneys rise from the east and west sides of the center of its gabled roof, which features a central, intersecting gable on the south facade, holding a roman arched, two-over-two light, double hung, attic window.

A two story high, bay window is located on the north side of its east wall.

A one story high, hipped roof, open porch runs along the entire south elevation and half of its east wall, supported by nine wooden columns, while a smaller hipped roof, open porch, supported by two square posts, covers the four light rectangular kitchen entrance on the north wall of that wing.

Fenestration is vertically aligned and proportionally scaled. Windows are double-hung, holding two-over-two lights, decorated with shutters and underlined by projecting wooden sills.

A wide, central, double entrance door is located on the south elevation, flanked by two vertical side lights and surmounted by a three light transom.

The house is notable as the home which was constructed in 1905 by Christian Ekert, who operated The Howard House in Ellicott City and later as the home of Michael Sullivan, historian and well beloved Post Master of Ellicott City.

# Maryland Historical Trust State Historic Sites Inventory Form

# MARYLAND INVENTORY OF HISTORIC PROPERTIES

Survey	No.	HO-344
--------	-----	--------

Magi No.

DOE \_\_yes \_\_no

1. Nam	le (indica	ite preferre	ed name) Cor	nley House			
historic Ecker	t House, Sull	ivan House,	Handwerk Hou	se			
and/or common	Conley Hou	ıse					
2. Loca	ation						
street & number	. 4919 Mont	gomery Road	(MD 103)			_ not for pub	lication
city, town	Ellicott	City _	vicinity of	congressional di	strict	Sixth	
state	Maryland		county	Howard			
3. Clas	sificatio	n				<del></del>	
Category  district building(s) structure site object	Ownership  public private both Public Acquisiti in process being consid x not applic	ion Acce	occupied unoccupied work in progress essible yes: restricted yes: unrestricted	Present Use agriculture commercia educationa entertainm governmer industrial military	al al ent	museun park private religiou scientifi transpo other:	residence s ic
4. Own	er of Pro	perty	(give names a	nd mailing add	resses	of <u>all</u> ow	ners)
name	Michele and	Jeffrey Con	nley				- ::
street & number	4919 Montgon	mery Road		telepho	one no.	:	
city, town	Ellicott Cit	У	state	and zip code	Maryla	nd 21043	·
5. Loca	ation of L	egal D	escription	on		21045	
courthouse, regis	stry of deeds, etc.	Howard Co	ounty			liber 19	932
street & number		8360 Cour	t Avenue				56
city, town		Ellicott	City		state Ma		
6. Repr	<u>esen</u> tati	on in E	xisting	Historical			
title							
date				federal	state	county	local
pository for sui	rvey records						
city, town		<del></del>			state		

7.	Des	crii	otio	n

Survey No. HO-344

Condition  X excellent deteriorated good ruins fair unexposed	Check one unaltered x altered	Check one  X original site moved date of move	
---	-------------------------------	---	--

Prepare both a summary paragraph and a general description of the resource and its various elements as it exists today.

Located on 1.5 acres on the north side of Montgomery Road east of the intersection of Route 103, this 2 1/2 story late-Victorian house was built about 1890. Arranged in a massed plan, three bays long and two bays wide with an ell, the gabled structure displays the popular rural vernacular center gable and wrap-around porch.

The facade is dominated by a center gable which holds a round-arch window. The windows are placed symmetrically around center six-paneled door with a narrow transom and sidelights. There are windows in both gables and a bay window in the second story north bay on the east side.

The hipped roof porch, which runs along the front, or south, side and east side, is supported by round columns and has a tongue and groove board floor. The porch is raised and rests on brick piers linked by a lattice apron.

Windows are all double hung 2/2 sash with the exception of the two flank the front door which are elongated 2/4 sash. The ell is two bay long and one bay wide and joins the main block at the east end of the north side.

Corbelled brick chimneys interrupt the roof ridge on the gable ends and on the gable end of the ell. The house has a raised random fieldston foundation and vinyl siding, probably placed over clapboards.

A front drive circles four mature oak trees which help separate the house from the busy thoroughfare and contribute to its 19th century character.

<u>8. \$</u>	8. Significance			Survey No. HO-344			4		
	istoric _ 	archeology-prehistoric archeology-prehistoric archeology-historic agriculture X architecture art commerce communications	C COI COI ecc edu eng exp ind	mmunity nservati onomics ucation gineerin oloratio	y planning ion s	la lit m m at ph	erature Ilitary uslc	- - nent _	religion science sculpture social/ humanitarlan theater transportation other (specify)
Specific	dates		Builder	/Archit	lect				
check:	and	able Criteria:A /or able Exception:	<del></del>		<del></del>	EF	G		
	Level	of Significance: _	_nation	al _	_state	_loca	1		
Prepare	both a	summary paragraph	of sign	ifica	nce and	a gene	ral statem	ent of	history and

This house is representative of the rural vernacular architecture in the

This house is significant as one of the last remaining examples of late 19th century Victorian rural vernacular architecture along Montgomery Road.

Statement continued. See attached.

County.

# 9. Major Bibliographical References

Survey No. HO-344

Howard County Land Records

10. Ge	ograpl	nical Data				
Acreage of nomic Quadrangle name	ne <u>Savage</u> ,	MDomplete UTM refer	ences		Quadrangle	e scale 1:24000
A	ing	Northing	B Zone	East	ing	Northing
C			D	J		
Verbal bounda Tax Maj Block S Parcel	p 31 8	on and justification				
List all states	and countie	s for properties over code	county	county	boundaries	code
state		code	county			code
11. Fo	rm Pre	pared By				
name/title	-	n, Historic Sites unty Department o				
organization	Planning a	and Zoning		date	November	1991
street & number	3430 Cc	ourthouse Drive		telepho	ne (410)	313-2037
city or town	Ellico	t City		state	Maryland	

The Maryland Historic Sites Inventory was officially created by an Act of the Maryland Legislature to be found in the Annotated Code of Maryland, Article 41, Section 181 KA, 1974 supplement.

The survey and inventory are being prepared for information and record purposes only and do not constitute any infringement of individual property rights.

return to:

Maryland Historical Trust

Shaw House

21 State Circle

Annapolis, Maryland 21401

(301) 269-2438

MARYLAND HISTORICAL TRUST DHCP/DHCD 100 COMMUNITY PLACE CROWNSVILLE, MD 21032-2023 301-514-7600 4919 Montgomery Road HO-344 Significance Statement Continued

Deed records show that the property was originally part of a large estate known as Chew's Resolution Manor and Chew's Vineyards, a land grant property comprising hundreds of acres. In 1874 Mary Dorsey subdivided the land, selling Lots 2, 4, 5 and 6 totaling 240 acres to James Clark. In 1891 Clark bought Lot 3, totaling 82 acres, then sold the lot that now contains this house to William Davis Jr. After examining its style and the deeds, it is probable that the house was constructed after this sale. Between 1924 and 1988 the property shrunk from 31 acres to less than two acres as suburban development sprung up around it.

Montgomery Road has historically been an important thoroughfare in Howard County linking Ellicott City (via Columbia Pike) with Elkridge, once a major inland port. Today the house represents the last vestige of a rural environment along what is now a densely developed corridor. While the lot is small the mature trees provide a buffer from the road. With the exception of artificial siding, the house retains its 19th century integrity.

Conley House 4919 Montgomery Road HO-344

#### HISTORIC PERIOD CONTEXT:

Region:

Piedmont

Period:

Industrial/Landscape Architecture and Community

Planning

Theme:

Architecture, Landscape Architecture and Community

Planning

Resource Type: Residence/rural vernacular

Site Types:

Standing structures

#### MARYLAND HISTORICAL TRUST

### INVENTORY FORM FOR STATE HISTORIC SITES SURVEY

NAME			
HISTORIC			
AND/OR COMMON The Handwerk Ho	use		
LOCATION			
STREET & NUMBER 4919 Montgomery R	coad		
CITY. TOWN Ellicott City		CONGRESSIONAL DISTRI	СТ
STATE	VICINITY OF	COUNTY	
Maryland		Howard	
CLASSIFICATION			
CATEGORY OWNERSHIP	STATUS	PRES	ENT USE
DISTRICTPUBLIC	X_OCCUPIED	AGRICULTURE	MUSEUM
X.BUILDING(S) X PRIVATE	_UNOCCUPIED	COMMERCIAL	PARK
STRUCTUREBOTH	WORK IN PROGRESS	EDUCATIONAL	X PRIVATE RESIDEN
SITE PUBLIC ACQUISITIO		ENTERTAINMENT	RELIGIOUS
OBJECTIN PROCESS	X_YES: RESTRICTED	GOVERNMENT	SCIENTIFIC
BEING CONSIDERED	YES: UNRESTRICTED NO	INDUSTRIAL MILITARY	TRANSPORTATION
NAME Mary L.W.C. and Mark H	. Handwerk	Telephone #:	
4919 Montgomery Road			
CITY TOWN Ellicott City	VICINITY OF	Maryland	ip code 21043
LOCATION OF LEGAL DES	CRIPTION	Liber #: 698	
courthouse.  REGISTRY OF DEEDS, ETC. Hall of Record	Tax Map 31, p. 309	Folio #: 614	
STREET & NUMBER Howard County	Court House		
CITY, TOWN		STATE	<del></del>
Ellicott City			aryland
REPRESENTATION IN EXIS	STING SURVEYS		
TITLE Howard County Historic Si	ites Inventory		
DATE 1978-1979		ASTATECOUNTYLOCAL	
DEPOSITORY FOR SURVEY RECORDS Maryland Historic			
CITY, TOWN		STATE	
	Annapolis	Man	yland

## 7 DESCRIPTION

X EXCELLENT

\_GOOD

\_\_FAIR

CONDITION

\_\_DETERIORATED

\_\_RUINS

\_\_UNALTERED

CHECK ONE

XALTERED

\*\* ORIGINAL SITE ....MOVED DATE\_

#### DESCRIBE THE PRESENT AND ORIGINAL (IF KNOWN) PHYSICAL APPEARANCE

The Handwerk House faces south on the north side of Montgomery Road, just east of its intersection with Route 104.

It is a three bay wide, two room deep, two and a half story high, frame (covered with asbestos shingles), gabled roof (running east-west) house, resting on a stone foundation. Square, brick, corbeled chimneys rise from the east and west sides of the center of its gabled roof which features a central, intersecting gable on the south facade, holding a Roman arched two-over-two light, double-hung attic window. A two story high, bay window is located on the north side of its east wall. Extending from the east side of the north wall is a two bay wide, one room deep, two story high, intersecting gable roof (running north-south) frame kitchen wing.

A one story high, hipped roof, open porch runs along the entire south elevation and half of its east wall, supported by nine wooden columns.

A smaller hipped roof, open porch, supported by two square posts covers the four light, rectangular kitchen entrance in the east bay of the kitchen wing's north wall. Six wooden steps lead to its landing, while four wooden steps on its west wall lead to the semi-enclosed porch created in the northwest corner of this kitchen section. A square brick chimney is centered into the north wall of the kitchen wing.

Fenestration for the house is vertically aligned and proportionally scaled. Windows are double-hung, holding two-over-two lights, decorated with green shutters and underlined by projecting wooden sills. One three light basement window is inset into the east and north walls of the house, and two similar ones in its west foundation wall, which holds the cornerstone marked "C.E. 1905" on its south side. Tall rectangular, first floor windows, featuring two-over-four lights, flank the double, wooden paneled, central entrance door on the south elevation.

This wide entrance is surmounted by a three light transom, flanked by two vertical side lights, and leads into a vestibule which features a double paneled entrance, also surmounted by a three light transom and flanked by two vertical side lights.

This interior entrance, in turn, leads into the central hall, which holds a fine staircase, featuring curvilinear spindles and supporting Knewel post.

Interior cross paneled doors are flanked by fluted pilasters and surmounted by fluted wooden lintels, joined at their corners by squares decorated with rosettes. The most interesting feature of these interior doors, however, are their two-light transoms, which can be opened to provide circulation as well as light, while allowing doors to be closed for privacy.

Floors are constructed of  $3\frac{1}{2}$  inch pine boards. The fine mantlepiece in the dining room, located in the northeast corner of the front section of the house, features an architrave decorated with curvilinear garlands.

The kitchen wing features an enclosed staircase leading up to a bedroom and bath in that section of the house.

#### 8 SIGNIFICANCE

PERIOD —PREHISTORIC —1400-1499 —1500-1599 —1600-1699 —1700-1799 —1800-1899 —1900-	AF  _ARCHEOLOGY-PREHISTORIC  _ARCHEOLOGY-HISTORIC  _AGRICULTURE  &ARCHITECTURE  _ART  _COMMERCE  _COMMUNICATIONS	REAS OF SIGNIFICANCE CH  COMMUNITY PLANNING  CONSERVATION  ECONOMICS  EDUCATION  ENGINEERING  EXPLORATION/SETTLEMENT  INOUSTRY  INVENTION	LANOSCAPE ARCHITECTURE  LAW  LITERATURE  MILITARY  MUSIC  PHILOSOPHY  POLITICS/GOVERNMENT	RELIGIONSCIENCESCULPTURESOCIAL/HUMANITARIANTHEATERTRANSPORTATION X_OTHER (SPECIFY)Local_History
SPECIFIC DAT	<b>ES</b> 1905	BUILDER/ARCH	HITECT	

STATEMENT OF SIGNIFICANCE

The Handwerk House is significant architecturally to the State of Maryland and Howard County as an example of the Romanesque style as represented in American domestic architecture of the late nineteenth and early twentieth centuries. It is also significant historically as the home of Christian Eckert, owner and operator of the historic Howard House in Ellicott City, who constructed the house in 1905, and of Michael Sullivan, local historian and beloved Postmaster of Ellicott City, who bought the house on Montgomery Road in 1924, and remained there with his large family for sixteen years. The following description of the house and Sullivan Family is given on page 67 of a small booklet entitled, The Family Sullivan, written by Joseph Howard Nichols, a grandson of Michael James Sullivan (1875-1945).

The house was to be home to Mike and his family for sixteen years (1924-1945). Much family history took place during this era. In addition to Mike, Rose and children, the house was also home to two friends and one relative. The latter was Broyderick Laffy, Rose's brother, who lived with the Sullivans until his death in 1939. Uncle Doc, as he was called, did much of the work on the property, as well as housework and helping in the kitchen. Another indication of Mike's good will is the two friends who lived and ate free of charge.

It should be mentioned here that the Sullivan family also provided two rooms in the house to Christian and Emma Eckert, from whom they had purchased the house for \$6,000. They remained with the Sullivan family until their deaths.

The dialogue in the booklet continues with a brief description of Mike's dog, Governor, who was trained to bring his slippers down from the bedroom, and to bring in the daily newspaper; to a description of Mike's garden, where he spent many hours. It continues with the following interesting data on auxiliary buildings on the property. This description is significant for it gives us a picture of the customs and habits of Howard Countians during this period of time. Tenant houses produced additional income for property owners. Such a tenant house, once located on the property, then comprising 31 acres, produced \$180 per year income. In addition, the property then consisted of another tenant house, a pump house, a barn (later a garage), and the main house, consisting of 12 rooms, a bath and a large front porch.

The barn produced additional income for the Sullivans in an unusual way. It was the custom of Howard Countians to attend cock fights on Saturday evenings during different periods each year. Mike Sullivan sponsored such activities, in the old

CONTINUE ON SEPARATE SHEET IF NECESSARY

barn, which drew large crowds, including the wealthy, who were charged admission. It was noted by his grandson that Mike never permitted members of his family to attend these cock fights, which were illegal.

For nineteen years, Michael Sullivan served Howard County as Clerk to the County Commissioner (1911-1930), for five years as newspaper man for The Times in Ellicott City (1930-1935), and later, in July, 1936, at the age of 61, became acting Ellicott City Postmaster, made permanent on May 17, 1937. He served in that capacity until his death in 1945.

Not only the Eckert and Sullivan families have contributed to the historical significance of this house, but the present owners today make their own unique contribution. Mrs. Handwerk is the daughter of Mary Levina Owings, fourth direct descendant of the first Governor of Maryland, Thomas Johnson, who nominated George Washington as Commander-In-Chief, and who was one of three Marylanders to serve on the U.S. Supreme Court.

In conclusion, the Handwerk House is significant to Howard County and the State of Maryland as the home of Christian and Emma Eckert, who operated the Historic Howard House in Ellicott City, renowned for its fine German cuisine; secondly, as the home of Michael Sullivan, local writer and historian of note, who served over a quarter of a century as a responsible and dedicated public servant to Howard County and Ellicott City, Maryland; and thirdly, as the present home of a direct descendant of Thomas Johnson, the first Governor of Maryland, and one of three Marylanders to serve on the U.S. Supreme Court.

Through the history written by Michael Sullivan's grandson, we also receive a vivid picture of the growth and development of an Irish immigrant family and its complete assimilation into the life of the United States as represented in Howard County, Maryland, culminating in one of its members actively engaged in career government service and recognized as a distinguished local historian.

Additionally, the house is noteworthy architecturally as representative of the Romanesque Revival, which took place in American domestic architecture during the last half of the nineteenth century and the early decades of the twentieth. The roman arched attic window inset into its central intersecting gable is representative of this style. Many such houses, similarly constructed, dot the Howard County landscape. All are significant in recalling a period of stylistic architectural history in America.

For these reasons, the Handwerk House is of outstanding significance to Howard County and the State of Maryland, and should be considered for inclusion in the National Register of Historic Places, the State Critical Areas Program, and any local landmark ordinance the citizens of Howard County may seek to initiate.

HO-344 Dist. 2

#### 9 MAJOR BIBLIOGRAPHICAL REFERENCES


Interview with Mrs. Mark Handwerk, April 2, 1979 Land Records of Howard County, Maryland Nichols, Joseph Howard, The Family Sullivan, Rockville, 1977


CONTINUE ON SEPARATE SHEET IF NECESSARY	
10 GEOGRAPHICAL DATA	
ACREAGE OF NOMINATED PROPERTY 2.132 acres	•
Please see Attachment 1, Tax Map 31, p. 309	
	•
VERBAL BOUNDARY DESCRIPTION	<del></del>
Please see Howard County Land Records, Liber69	98 <b>Folio</b> 614
•	
LIST ALL STATES AND COUNTIES FOR PROPERTIES OVERLAPPING STATE OR COL	LINTY BOLLNDADIES
LIOT ALL STATES AND COOKTIES FOR TROPERTIES OVERLAPPING STATE OR CO.	DINTI BOUNDARIES
STATE Maryland COUNTY Howard	
<u> </u>	
STATE	
11 FORM PREPARED BY	
NAME/TITLE Cleora Barnes Thompson, Archivist	
ORGANIZATION DATE	
Office of Planning & Zoning-Comprehensive Planning Section	
STREET & NUMBER TELE	PHONE
3450 Court House Drive	
CITY OR TOWN STAY Ellicott City	
	Maryland


The Maryland Historic Sites Inventory was officially created by an Act of the Maryland Legislature, to be found in the Annotated Code of Maryland, Article 41, Section 181 KA, 1974 Supplement.

The Survey and Inventory are being prepared for information and record purposes only and do not constitute any infringement of individual property rights.

RETURN TO: Maryland Historical Trust
The Shaw House, 21 State Circle
Annapolis, Maryland 21401
(301) 267-1438









H 34-344 Hewers Rounty, M.D. AMI WORDEN 1) NO SHEL



Ho-344
The Handwerk Hoose
South east
CB Thompson, AICP
APRIL, 1979